

## Notes on transport, storage and assembly of ROMA quick-assembly insulating panels

<p><b>Deliveries</b></p>	<p>The truck driver shares responsibility for proper loading of the truck and for suitable transport.</p> <p>Prior to loading, please check to make sure the elements have arrived undamaged.</p> <p>Check the shipment for completeness and for any transport damage.</p> <p>Immediately report any complaints directly during acceptance and enter the complaints and the name of the driver and truck license plate number in the shipping documentation.</p>
<p><b>Unloading</b></p>	<p>Work with particular care during unloading and placing into storage!</p> <p>When unloading with a crane, always use belts and the supplied unloading <b>planks</b>. Place the planks on the places marked in red!</p> <p>Always use <b>traverses</b> if panel lengths are <b>greater than 10m</b>.</p> <p>Never unload two bundles at the same time.</p> <p>For closed trucks, remove the tarpaulins to unload.</p> <p>If unloading is done with a forklift truck, the truck driver must monitor this carefully. It is the responsibility of the truck driver to hand over shipment without damage.</p>
<p><b>Storage</b></p>	<p>Store the bundles on a <b>flat surface</b> with enough suitable material underneath them. Stack bundles no more than two high.</p> <p>Protect the panel bundles from sun exposure and moisture by covering them with foils or tarpaulins.</p>
<p><b>Protective foils</b></p>	<p>Completely remove the protective foils immediately after assembly, on the same day at the latest.</p> <p>Protective foil on the roof and wall elements are only designed for short-term storage. The adhesion of the protective foils on the panel surfaces constantly increases. Therefore, take special care to safeguard the protective foil from sun exposure.</p>
<p><b>Assembly</b></p>	<p>The relevant regulations for assembly of sandwich panel elements (issued by IFBS Düsseldorf) must be observed during assembly.</p> <p>The accident prevention regulations and safety regulations for assembly of roof and wall sandwich panel elements must be observed.</p> <p>Only use cutting tools which work without flying sparks and substantial heat build-up.</p> <p>Immediately remove metal burrs, rivets and other foreign objects.</p> <p>Be careful about sharp edges and hazardous edges which cannot be avoided on the panels.</p>
<p><b>No warranty is extended for any damage resulting from failure to observe these notes!</b></p>	